

Duplex Pump Control Panel — Three-Phase · Quick Start

230 VAC · 3-Phase | Duplex · Automatic Alternation | 3 HP · Float Control

DESIGNED & MANUFACTURED BY LEGACY CONTROLS · MIMS, FLORIDA · UL 508A LISTED

GUIDE VERSION 1.1

DATE August 2026

MODEL LC-9100 · 9000 Series Three-Phase Duplex

UL FILE NUMBER E547664

FULL DOCUMENTATION Operation Manual v1.1 · Spec Sheet v1.1

DRAWINGS Schematic Set Sheets 1–5 · Rev C (As-Built)

⚠ READ FIRST — 230 V 3-PHASE SUPPLY & CONTROL TRANSFORMER

This panel operates on 230 VAC three-phase — three phase conductors plus ground; no incoming neutral. The 120 V control circuit comes from control transformer T1, configured for a 230 V primary (jumpers H1–H3 and H2–H4). Verify the jumpers and confirm supply voltage with a voltage tester before energizing. **Verify pump rotation before placing the panel in service.**

1. BEFORE YOU ENERGIZE

- Mount** — secure the NEMA 4X enclosure (Polycase ZH-161407) to a stable vertical surface with clearance for the door and service access.
- Verify the transformer** — T1 primary jumpers H1–H3 and H2–H4 (230 V), with all fuses installed: F1/F2 1.25 A time-delay primary · F3 2 A alarm · F4 2 A control.
- Set the overloads** — dial each overload relay (9–12.5 A range) to the pump motor nameplate FLA — 3 HP pumps: 9.6 A.
- Land the pumps** — Pump 1 leads on terminals 4 / 5 / 6 plus ground · Pump 2 leads on terminals 7 / 8 / 9 plus ground.
- Install the floats** — N.O. floats lowest to highest: Off · On · Both-Pump · High Water Alarm. Terminal pairs: Off on 12 & 13 · On on 10 & 11 · Both-Pump on 14 & 15 · High Water Alarm on 16 & 17 — the Off float (lowest) lands on the higher-numbered pair. Every float gets its own terminal pair; never piggyback float leads.
- Torque & feed** — copper conductors, 60 °C minimum — DK4N field terminals 5.3 in-lbs (0.6 N·m); DK10N power terminals per the block marking. Feeder protection is field supplied at the main panel, with a main disconnect switch upstream.

2. START-UP & FUNCTIONAL TEST

- Check rotation** — bump each pump briefly in HAND and verify correct rotation. If reversed, de-energize, lock out, and swap any two phase conductors at that pump's load terminals — never at the incoming feed.
- Energize** — set both pump selectors to AUTO — with no faults present the alarm globe is off and both pumps are idle.
- Cycle the floats** — raise the On float — the lead pump starts, seals in for full drawdown, and stops when the level drops below the Off float. Confirm the lead/lag designation alternates after each cycle.
- Test high demand** — lift the Both-Pump float — both pumps run together until the level drops (pumps in AUTO only).
- Test the alarm** — lift the High Water Alarm float — the red globe and buzzer annunciate with NO pump action. Press the test pushbutton, then verify the silence switch: buzzer silences, globe stays lit. Return both selectors to AUTO before leaving.

3. ALARMS & INDICATORS

- Green run lights** — illuminate whenever the respective pump is running.
- Red globe + buzzer** — high water — driven by the highest float on its own fused alarm branch (F3, which also feeds the Both-Pump float); it calls no pump. The silence switch interrupts the buzzer only; the globe stays lit until the level clears.
- Overload trip** — stops that pump with no alarm — a rising level brings the Both-Pump float, then the alarm float, into play. Identify and correct the cause before resetting the overload.

4. FACTORY SETTINGS — QUICK CHECK

TELE E1ZMLA10 load alternator — ships factory-configured; verify at commissioning and after any component replacement:

- **Function** — selector (P1) set to LA (Load Alternator) BEFORE energizing — the output transfers 18 ↔ 16 each time B1 is energized, so the lead pump swaps every pump-down cycle. The output common (15) is fed by the pump call, never from constant 120 V.
- **Delay** — both time knobs (P2 range, P3 value) fully counter-clockwise for the standard minimum ≈ 50 ms de-bounce.
- **Verify** — green U/t LED confirms supply; yellow R LED illuminated = Pump 2 is the selected pump. L1 / L2 manual modes are for service only — return the selector to LA.
- **Overloads & fuses** — overload dials at 9.6 A · F1/F2 1.25 A time-delay primary · F3 2 A alarm · F4 2 A control.

5. SERVICE & SUPPORT


SERVICE & SUPPORT Contact the authorized dealer or installer who supplied your system for all technical support, service calls, alarm response, and warranty claims — their information is recorded on the Service & Support card at the front of the Operation Manual. **If your dealer cannot be reached, visit [Legacy-Controls.com](https://www.legacy-controls.com).**

LC-9100 DUPLEX PUMP PANEL — SCHEMATIC SET · TERMINAL DIAGRAM

SHEET 1 OF 5 · REV C (AS-BUILT)

INCOMING 230 V 3Ø				PUMP 1 (M1)				PUMP 2 (M2)			
G DK10N-PE GND / PE	1 DK10N LEG 1	2 DK10N LEG 2	3 DK10N LEG 3	G DK4N-PE P1 GND	4 DK4N M1 T1	5 DK4N M1 T2	6 DK4N M1 T3	G DK4N-PE P2 GND	7 DK4N M2 T1	8 DK4N M2 T2	9 DK4N M2 T3
FLOATS — 4 x 2-WIRE, 120 V											
10 DK4N ON FLT	11 DK4N ON FLT	12 DK4N OFF FLT	13 DK4N OFF FLT	14 DK4N BOTH-PMP	15 DK4N BOTH-PMP	16 DK4N ALM FLT	17 DK4N ALM FLT				
NEUTRAL BANK + LV GND				CONTROL FUSES				RELAYS			
N DK4N NEUTRAL	N DK4N NEUTRAL	N DK4N NEUTRAL	G DK4N-PE LV GND	F3 DINKLE FUSE TERM 2 A — ALARM	F4 DINKLE FUSE TERM 2 A — CONTROLS			R1 DINKLE SPDT CUBE RELAY FLOAT RELAY	R2 DINKLE DPDT CUBE RELAY BOTH-PUMP		

1 — POWER CIRCUIT · 230 VAC 3Ø 60 Hz



CB1 / CB2 — 30 A 3-pole pump branch breakers · **C1 / C2** — HIITIO HC5-16 contactors · **OL1 / OL2** — 9-12.5 A thermal overloads · **M1 / M2** — pump motors 3 HP / 10 A, 230 V 3Ø, leads on terminals 4-5-6 / 7-8-9.

CB3 — 2-pole control feeder off terminals 1 & 3 · **F1 / F2** — 1.25 A Bussmann CC time-delay · **T1** — 230/120 V control transformer · **F3 / F4** — 2 A alarm / control fuses · X2 → N-N-N bank, bonded at LV G terminal.

LC-9100 DUPLEX PUMP PANEL — SCHEMATIC SET · CONTROL LADDER — RUNGS 1-3


SHEET 3 OF 5 · REV C (AS-BUILT)

LEFT RAIL = WIRE 101 CONTROL HOT (F4) · RIGHT RAIL = WIRE 102 NEUTRAL N-N · ON FLOAT = 10/11 · OFF FLOAT = 12/13

C — 120 VAC CONTROL LADDER · ALL COIL AND CONTACT TERMINALS SHOWN

WIRE 101 · CONTROL HOT (F4)

WIRE 102 · NEUTRAL BANK N-N (X2)




CONTROL WIRE SCHEDULE — EVERY LANDING

- 101 Control hot (F4 load) — R3 A1 · R2 11 · R2 21 · SS1 scr 1 · SS2 scr 1 · C1 aux 13 · C2 aux 13 · **terminal 13**
- 102 Neutral bank N-N (T1 X2) — R1 A2 · R2 A2 · R3 A2 · C1 A2 · C2 A2 · PL1 neutral · PL2 neutral · AL1 neutral · BZ1 neutral
- 103 Alarm hot (F3 load) — **terminal 16** → **terminal 15** (jumper, feeds both-pump float) · PB1 scr 1
- 104 Off-float-made bus — **terminal 12** → **terminal 11** (jumper) · R1 pin 3
- 105 Pump call / R1 seal — **terminal 10** · R1 coil A1 · R1 pin 4 · R3 B1 · **R3 15**
- 106 Both-pump call — **terminal 14** · R2 coil A1
- 107 Pump 1 auto feed — R3 18 · SS1 scr 3
- 108 Pump 2 auto feed — R3 16 · SS2 scr 3
- 109 Pump 1 override — R2 14 · SS1 scr 3 (lands with wire 107)
- 110 Pump 1 coil feed — SS1 scr 2 · SS1 scr 4 · OL1 95
- 111 Pump 1 coil — OL1 96 · C1 A1
- 112 Pump 2 override — R2 24 · SS2 scr 3 (lands with wire 108)
- 113 Pump 2 coil feed — SS2 scr 2 · SS2 scr 4 · OL2 95
- 114 Pump 2 coil — OL2 96 · C2 A1
- 115 Alarm node — **terminal 17** · PB1 scr 2 · AL1 line · SS3 scr 1
- 116 Buzzer feed — SS3 scr 2 · BZ1 line
- 117 Pump 1 run light — C1 aux 14 · PL1 line
- 118 Pump 2 run light — C2 aux 14 · PL2 line

LC-9100 DUPLEX PUMP PANEL — SCHEMATIC SET · CONTROL LADDER — RUNGS 4-8

SHEET 4 OF 5 · REV C (AS-BUILT)

LEFT RAIL = WIRE 101 CONTROL HOT; LOWER LEFT RAIL = WIRE 103 ALARM HOT (F3) · RIGHT RAIL = WIRE 102 NEUTRAL



SCHEMATIC SET SHEET 4 OF 5 · CONTROL LADDER RUNGS 4-8 · REV C (AS-BUILT)

DEVICE SCHEDULE — CONTROL CIRCUIT

CB3 — 2-pole breaker, control transformer feeder off terminals 1 & 3 (leg 1 / leg 3 of the utility service).

F1 / F2 — Dinkie fuse terminals on the T1 primary. 1.25 A Bussmann Class CC time-delay, one per leg.

T1 — control transformer, 230 V primary (H1/H2) / 120 V secondary (X1/X2). Casing bonded to the LV “G” terminal.

F3 — Dinkie fuse terminal, 2 A, alarm branch only (wire 103).

F4 — Dinkie fuse terminal, 2 A, control branch (wire 101).

R1 — float relay, Dinkie plug-in cube, **SPDT**. **Coil = A1** /

A2, 120 VAC. Seal contact = socket pins 3 (common) and 4 (NO); pin 4 jumpers to coil A1. Dry contact, not a coil terminal.

R2 — both-pump activating relay, Dinkie plug-in cube, **DPDT**. **Coil = A1 / A2, 120 VAC**. Pole 1 = 11 com / 12 NC / 14 NO; pole 2 = 21 com / 22 NC / 24 NO.

R3 — Tele E1ZMLA10 alternating relay. **A1 / A2 = 120 VAC supply coil**. **B1 = control input signal terminal** (it is fed 120 V, it is not a second coil). Output changeover contact 15 com / 18 A / 16 B — one side is ALWAYS closed, so 15 is fed from the pump call (wire 105), never from constant 120 V. Dial set to LA.

C1 / C2 — pump contactors for M1 / M2, 120 VAC coils on terminals A1 / A2. Aux contact 13-14 (NO) closes when the contactor pulls in.

PL1 / PL2 — green pilot lights on the HOA switch panel, 120 V. Lit through C1 / C2 aux 13-14 — ON = coil locked

in, pump running.

OL1 / OL2 — thermal overloads on M1 / M2. Only the 95-96 NC trip contact is used in the control circuit; 97-98 NO is spare.

SS1 / SS2 — 3-position HAND-OFF-AUTO rotary selectors, HBDY5-KW-11X/31/201, Yueqing Dahe Electric. Screws 1-2 = HAND, screws 3-4 = AUTO.

SS3 — 2-position alarm silence rotary, HBDY5-KW-11X/201, same maker. Screws 1-2 closed in NORMAL.

PB1 — momentary push button, HBDY5-KW-10/W/201, Yueqing Dahe Electric. NO contact, screws 1-2.

AL1 — Ingram 25-LG alarm globe, 120 V.

BZ1 — piezo buzzer alarm, 95 dB, 120 VAC, 50 mA max, warble tone.

NOTES

- Every float lands on its own pair of DK4N terminals — no piggybacking of float leads. The 12 → 11 jumper (wire 104) and 16 → 15 jumper (wire 103) are panel-side, not field leads.
- Jumper SS1 scr 2 to scr 4 (and SS2 scr 2 to scr 4) so HAND and AUTO share one output to the overload.
- Jumper R1 socket pin 4 back to coil terminal A1 to form the seal-in; the same node carries out to R3 B1 and R3 15.
- Wires 107 and 109 both land on SS1 scr 3 (108 and 112 on SS2 scr 3) — use a twin ferrule or a bridged pair.
- Set the E1ZMLA10 function dial to LA before energizing, or the outputs will not alternate.
- F3 keeps the alarm alive if F4 opens. Never fuse the grounded conductor on the N bank.
- SS3 silences BZ1 only — AL1 stays lit until the level drops off the alarm float.
- PB1 feeds wire 115 only; it cannot start a pump in any selector position.